REQUEST FOR SUPPLEMENTAL SCOPE APPROVAL

Prepared for: State Farm Claims Department

Insured: Insured Property
Claim #: 49-1029-A
Risk Property: Job Site, San Diego, CA
Date of Loss: March 15, 2026
Assigned Adjuster: Sarah Jenkins
Policy Deductible: $1,000

Dear Sarah Jenkins,

Upon initial physical inspection and photographic deck verification for the above-referenced property, our project management team identified critical scope items omitted from the carrier's initial estimate that are required by local building code and manufacturer installation guidelines:

XACTIMATE / ITEM CODE	DESCRIPTION & BUILDING CODE JUSTIFICATION	QTY	UNIT COST	TOTAL
RFG DRIP	Galvanized Drip Edge Flashing (CBC § 1507.2.9.3)	220 LF	$4.25	**$935**
RFG VALM	Valley Ice & Water Shield / Metal (CBC § 1507.2.8.2)	65 LF	$6.50	**$422.5**
RFG STAR	Starter Strip Course - Universal High-Tack	220 LF	$2.80	**$616**
RFG PITCH	Steep Pitch Labor Surcharge (>7/12 slope)	32 SQ	$28.00	**$896**
			TOTAL REQUESTED SUPPLEMENT:	**$2,869.5**

> **Adjuster Field Documentation Notes:**
> California Building Code § 1507.2.9.3 mandates perimeter drip edge.

Photographic damage and deck verification photos have been archived in the project record and are available for review via the live project album: View Verified Photos.

Please review and issue a revised Scope of Loss reflecting these additions at your earliest convenience so construction may proceed without delay.